

## Code Forum

No. 97-01 Issuing Office: CEMP-CE Issue Date: 11 MAR 97 Exp. Date: 31 DEC 99

**CEMP-C** 

Subject: Requirements for Testing, Adjusting and Balancing of HVAC Systems

Applicability: Information

References: CEGS 15990, Testing, Adjusting and Balancing of HVAC Systems

Associated Air Balance Council (AABC), National Standards
National Environmental Relanging Purpose (AIERD), National Standards

National Environmental Balancing Bureau (NEBB), National Standards Civil Engineering Maintenance Inspection Repair Team (CEMIRT),

Preacceptance Reports

Sheet Metal And Air Conditioning Contractors National Association

(SMACNA), HVAC System TAB Manual

**Discussion:** Feedback from the Air Force CEMIRT Preacceptance Reports and Design Construction Evaluation (DCE) inspections indicate that problems with HVAC systems continue. CEMIRT personnel have made a series of preacceptance inspections on projects constructed by the Corps over the past ten years. The results are available in reports. Although there are a number of areas addressing design issues, there are also a number of apparently systemic issues in the construction area. Primary among these are the testing, adjusting and balancing (TAB) of HVAC systems. A Process Action Team (PAT) meeting was held 09-11 July 1996 to evaluate recommendations for improving enforcement of TAB of HVAC systems. Several recommendations of the PAT have been incorporated into CEGS 15990. The following is a list of changes to CEGS 15990 that will be in future contracts:

- a. TAB firm's current Certification by AABC or NEBB can be confirmed by a phone call to either agency. Phone AABC at (202) 737-0202 or NEBB at (301) 977-3698.
  - b. TAB Specialist shall be certified by AABC or NEBB. Confirm by phone.
- c. A Design Review Report is required 14 days after approval of the TAB Firm and Specialist. Any discrepancies, noted in the report, that would prevent the proper balancing of the HVAC System shall be corrected through a joint effort of engineering and construction.
- d. A copy of Preliminary Checklists shall be submitted for each system signed by the TAB Specialist prior to start of TAB. Example of checklists are shown in NEBB and SMACNA HVAC TAB manuals. See figures 1 & 2.
- e. Contractor shall submit a TAB Verification Report. The TAB Specialist shall recheck ten percent of the measurements listed in TAB Report. The measurements selected for verification and the individuals that witness the verification test will be selected by the COR.
- f. The TAB Specialist and COR shall witness the Duct Leakage Test. The TAB Specialist shall certify that it was successfully completed. Deficiencies noted during leakage test,

that would prevent TAB from producing satisfactory results, shall be corrected thru a combined effort of engineering and construction.

g. TAB shall be performed in accordance with the requirements of the standard under which the TAB Firm's qualifications are approved. All recommendations and suggested practices contained in the TAB Standard shall be considered mandatory. AABC or NEBB National Standards now become part of each construction contract.

The new requirements will require the TAB Firm to be selected and approved early in the construction phase. The construction schedule should include certain phases of TAB work in the critical path.

Huntsville Training Course HVAC Systems TAB in FY 98 will use, as handouts, both NEBB and AABC Standards Manuals. A NEBB and AABC certified contractor will be part of the instructor staff. Each certified instructor will teach from their respective manual. One full day will be spent at a AABC certified lab for hands on instruction. These are some of the changes being implemented to improve enforcement of TAB of HVAC systems. This Code Forum has been fully coordinated with CEMP-ET. If there are any questions on TAB of HVAC systems my point of contact is CEMP-CE (202) 761-0205.

CHARLES R. SCHROER
Chief, Construction Division
Directorate of Military Programs

## FIGURE 1 Systems Ready to Balance CHECK LIST

		Ready				
		Yes	No	Date Corrected		
3. <b>H</b> 1	VAC Units and Built-up Units					
<b>a</b> )	General					
	Louvers installed					
	Manual dampers open and locked					
	Automatic dampers set properly					
	Housing construction-leakage					
	Access doors-leakage					
	Condensate drain piping and pan					
	Free from dirt and debris					
	Nameplate data					
b)	Filters					
	Type and size					
•	Number					
	Clean					
	Frame-leakage					
c)	Coils (Hydronic)					
C)						
	Size and rows					
	Fin spacing and condition					
	Obstructions and/or debris					
	Airflow and direction					
	Piping leakage					
	Correct piping connections and flow					
	Valves open or set		- +			
	Airvents or steam traps					
	Provisions made for TAB measurements					
d)	Coils (Electric)					
	Size and construction					
	Airflow direction					
	Duct connections					
	Safety switches					
	Obstructions ·					
	Free from debris					
	Contactors and disconnect switches					
	Electrical service and connections	!				
	Nameplate data	1				
e)	Fans	İ	į			
	Rotation					
	Wheel clearance and balance					
	Bearing and motor lubrication	!				
	Drive alignment					
	Belt tension		1			

LI				
		Yes	ady	Date
_	i) Face (continued)	148	No	Corrected
e	) Fans (continued)			
	Drive set screws tight		<b></b>	
	Belt guard in place			
	Flexible duct connector alignment			
	Starters and disconnect switches			· · · · · · · · · · · · · · · · · · ·
	Electrical service and connections			
	Nameplate data			
f)	Vibration Isolation			
	Springs and compression			
	Base level and free			
. Dı	uct Systems			
a)	General	<u>.</u>		
	Manual dampers open and locked			
	Access doors closed and tight			
	Fire dampers open and accessible			
	Terminal units open and set			
	Registers and diffusers open and set			*
	Turning vanes in square elbows			
	Provisions made for TAB measurements			
	Systems installed as per plans			
	Ductwork sealed as required			<del></del>
b)	Architectural			<del></del>
-•	Windows installed and closed			
	Doors closed as required			<del> </del>
	Ceiling plenums installed and sealed			
	Access doors closed and tight			
	Air shafts and openings as required			
D.,	imps			
	Motors		į	
۳,	Rotation			
	Lubrication			
	Alignment			
	Set screws tight			
	Guards in place			
	Tank level and controls			
	Starters and disconnect switches			
	Electrical service and connections			-
	Nameplate data			
b)	Piping			<u> </u>
	Correct flow			
	Correct connections	i	1	,

## FIGURE 2 Systems Ready to Balance (Continued) CHECK LIST

L V	Piping (continued) Leakage	Yes	No No	Date Corrected		•	Cooling Towers	Yes	No	Date Corrected
L V	Leakage									
S			1				Evaporative Condensers (continued)	<b></b>		
SAF	· · · · · · · · · · · · · · · · · · ·						Starters and disconnect switches			
A F	Valves open or set						Electrical connections	<u>.                                    </u>		
F	Strainer clean						Nameplate data			
P	Air vented				5.	Re	frigeration Equipment			
	Texible connectors				•			<u> </u>	<del></del>	· ·
С	Provisions made for TAB measurements						Crankcase heaters energized	ļ		
_	Cavitation possibilities						Operating controls and devices	<u> </u>		
c) B	Bases						Safety controls and devices	ļ		
V	/ibration isolation						Valves open			
G	Grouting						Piping connections and flow			
٠.	eveling						Flexible connectors	<del> </del>		
l. Hydro	onic Equipment	İ		ļ			Oil level and lubrication	<del> </del>		
a) B	Boilers						Alignment and drives	<u>  \</u>		
0	Operating controls and devices						Guards in place	<u> </u>	<del></del> -	
S	Safety controls and devices		i				Vibration isolation			
-	Lubrication of fans and pumps  Draft controls and devices						Starters, contactors and disconnect switches			
						•	Electrical connections	:		
	Piping connections and flow						Nameplate data	!		
-	/alves open or set  Vater make-up provisions					Line	dronic Piping Systems			
_	Water make-up provisions				0.	пу	uronic riping Systems	<u> </u>		
	Electrical connections						Leak tested	· •		
-	lameplate data						Fluid levels and make-up	<u> </u>		
-	leat Exchangers						Relief or safety valves	ļ		
_	Correct flow and connections						Compression tanks and air vents	•		;
_	/alves open or set		!				Steam traps and connections			
-	urvents or steam traps						Strainers clean	<u> </u>		
	eakage						Valves open or set	ļ	. ~ •	
	rovisions made for TAB measurements a						Provisions made for TAB measurements	<u>.</u>		
_	lameplate data			·			Systems installed as per plans			
c) G	Cooling Towers:				7.	Co	ntrol Systems		:	
_	vaporative Condensers		!				Data centers	<del>;</del>		
_	Correct flow and connections			<del></del>			Outdoor/return Air/reset	<del>!</del>		
-	/alves open or set		·				Economizer			
_	eakage		<u>i</u>				Static pressure	•		
-	rovisions made for TAB measurements						Room controls	*		·- ··· · · · · · · · · · · · · · · · ·
S	sump water level			<del></del>						
S	Spray nozzles		<u> </u>		8.	Oth	er Checks			
Fa	arvpump rotation	ļ				a)	Other trades or personnel notified	<del></del>		
M	fotor:fan lubrication						of TAB work requirements	•		
Di	Prives and alignment	· · · · · ·				b)	Preliminary data complete	·		
G	Suards in place					c)	Test report forms prepared	·		