THE U.S. ARMY YUMA PROVING GROUND 900-KVA PHOTOVOLTAIC POWER STATION


Roch Ducey, CECER, 217/398-5222

Richard Chapman, Sandia National Laboratories, 505/844-0859

Sam Edwards, Naval Air Weapons Station, China Lake, 760/939-1280

ABSTRACT

In the early spring of 1997, a 900-KVA, utility-tied photovoltaic power station was installed at the U.S. Army Yuma Proving Ground (YPG), in the southwest corner of Arizona (see Fig. 1). The system will be used to offset peak demand and serve as an emergency power system for YPG's water treatment plant. The power station includes 450-kWp of Siemens M-55 modules, 5600-kWh of C&D motive power batteries (see Fig. 2), and a 900-KVA power processing (see Fig. 3) and control system from Trace Technologies. Enhanced by the battery load leveling system, the power station has the capacity to reliably provide from 450- up to 825-KVA to YPG's utility grid during the summer peak demand season. The YPG system has three basic operating modes: (1) daytime utility-tied, (2) nighttime utility-tied, and (3) standalone. The amount of power delivered to the grid is governed by either available power from the PV array or by a power level



defined by the user, whichever is greater.





FIGURE 1. THE 450-KWP PHOTOVOLTAIC ARRAY

FIGURE 2. BATTERIES

FIGURE 3. POWER PROCESSING

INTRODUCTION

Yuma Proving Ground had a ribbon-cutting ceremony for its 900-KVA Photovoltaic Power Station, on March 25, 1997. The celebration marked the culmination of exactly five years of planning and working towards having this unique system installed. A number of U.S. Department of Defense (DoD) and Department of Energy (DOE) agencies have been directly involved with the project's implementation, since the initial concept development meeting on March 26, 1992 [1].

PROJECT HISTORY

A few months before that first meeting, YPG's Energy Manager contacted the U.S. Army Construction Engineering Research Laboratories (USACERL) for some advise about a projected 40% increase in use of electricity at YPG. Because of Base Realignment and Closure (BRAC), it had been determined that YPG would be a "gaining" facility, meaning that selected activities from other DoD installations would be moved to YPG. At that time, most of YPG's electricity was being provided as cheap hydroelectric power from the Western Area Power Administration (WAPA). However, YPG had already exceeded their WAPA increment and any load growth resulting from BRAC would have to be served by their local utility, Arizona Public Service (APS). APS's energy and demand rates were almost ten times WAPA's. addition, WAPA was instituting a new policy requiring its major customers to formulate Integrated Resource Plans (IRP), which included developing renewable energy resources. If the conditions of the IRP were not met, WAPA reserved the right to reduce the hydroelectric increment by 10%.

YPG knew that USACERL was the Army member of the DoD Photovoltaic Review Committee (PVRC) and that they might assist YPG in developing a PV project which would help with both its projected increase in electrical demand and its WAPA requirements. A utility-tied PV system is a renewable energy technology that could serve as peaking equipment because it would generate high-value electricity at the same time YPG experiences its peak demand, on summer afternoons when the sun is shining and all of the air conditioners are on. Normally, the cost of a PV system is too high to be competitive with conventional powerplants, even at APS's high rates. But when the benefit of avoiding the 10% decrease of cheap WAPA electricity was factored in, a utility-tied PV project became very attractive.

PROJECT FUNDING

Fortunately for YPG, Congress had just added \$6M, specifically set aside for renewable energy projects, to the existing \$30M DoD Energy Conservation Investment Program (ECIP). The PVRC was responsible for identifying appropriate PV projects and was looking for one to represent DoD in the DOE program, Photovoltaics for Utility Scale Applications (PVUSA). YPG and USACERL developed an ECIP proposal for a Phase I project, a 150-kWp Photovoltaic Peaking Plant with the ability to expand to as large as a 600-kWp PV array. The proposal was endorsed by the PVRC, designated its PVUSA project, and was eventually approved and funded.

SCALE AND CAPABILITIES OF THE YPG POWER STATION INCREASE

Since those early beginnings, the project has grown in size and also in recognition among the renewable energy community. When the project was turned over to Sacramento District Office of the U.S. Army's Corps of Engineers for design-build contractor selection, it was nominated and selected as one of DoD's Federal Energy Management Program Showcase Facilities. Additional ECIP funding was used to increase the size of the PV array to the present 450-kWp (DC side). The final design includes a one-axis tracking system (see Fig. 4) and the capability of operating in an isolated-grid, stand-alone mode. If there is ever an extended utility outage, the PV Power Station will continue to provide electricity to YPG's nearby water treatment plant.

In FY94, the Naval Air Weapons Station, in partnership with Sandia National Laboratories (the Navy and DOE members of the PVRC), initiated a development program to add battery load-leveling equipment, including an additional 450-KVA of power processing capacity [3]. This enhancement nearly doubles the plant's peak-shaving capacity from 450 to 825-KVA, ensures a



minimum peak-shaving capacity of 450-KVA during overcast or scattered cloud conditions, and provides back-up power to YPG's critical water treatment plant load, during utility outages [4].

FIGURE 4. SINGLE-AXIS TRACKING SYSTEM [2]

EQUIPMENT INSTALLATION

Sacramento District Office awarded the design-build contract to Utility Power Group in early 1996 and construction began later that year, under the supervision of the Los Angeles District Office. The construction schedule planned for the system to be operational by early spring of 1997, in time to have some impact on YPG's peak demand for the upcoming cooling season. However, several weeks of unseasonably hot weather in late February and early March caused the 1997 peak to be established before the 900-KVA PV Power Station was fully on line. Performance data on how well the system is able to peak shave will have to wait until the summer of 1998.


SYSTEM CONFIGURATION AND OPERATION

A block diagram of the YPG system (see Fig. 5) shows that the 900-KVA power processing system consists of two identical 450-KVA subsystems. Each 450-KVA subsystem consists of two 225-KVA inverter/rectifiers; a master and a slave. Each 225-KVA inverter/rectifier includes a 225-KVA PV maximum power tracker (MPT) and a 225-KVA bi-directional dc/dc converter for the

battery. The MPTs and the battery dc/dc converters allow the inverter/rectifiers to operate at a higher voltage than the PV array and battery. In this case, the inverter/rectifiers operate at 750 Vdc while the PV array operates at a nominal 375 Vdc and the battery operates at a nominal 432 Vdc. The higher inverter/rectifier voltage increases both the efficiency and capacity of the inverter/rectifiers. The PV array and battery are divided into two halves. One half of the array and battery feed the master MPTs and battery dc/dc converters, and the other half feeds the slave MPTs and battery dc/dc converters. The operating mode determines which MPTs, battery dc/dc converters, and inverter/rectifiers operate at any one point in time.

OPERATING MODES

The YPG system has three basic operating modes: (1) daytime utility-tied, (2) nighttime utility-tied, and (3) stand-alone. Whenever utility power is present, the system is either delivering power from the array and battery into the grid






FIGURE 5. BLOCK DIAGRAM


FIGURE 6. POWER PROFILE

power delivered to the grid is governed by either the available power from the PV array or by a power level defined by the user, whichever is greater. The user defines power levels via a programmable power profile.

The operating modes are illustrated using a typical array power profile for a summer day in Yuma (see white bars in Fig. 6) and an example user power profile (see bold line in Fig. 6). Note that the array power profile is the ac power that can be derived from the available dc power from the array. For this example, the user power profile is zero for hours 14 through 24 and hours 1 through 9, 450-kW for hours 10 and 11, and 750-kW for hours 12 and 13. This profile is used to tailor the output of the system to the site's demand characteristics. As stated above, the power


delivered to the grid is the greater of the available PV power and the power than the power that the power than the power than the power than the power than th For Power Richards System mple case, the user. PV Master pwer den the grid is PV Master ed by the awailable PV before hour 225-kWp (white 10 a 225-kWp ter hοι to grid o Master 1 mode, all battery de 225-kVA my 紫紫色rs water Arme are inactive 225-kVA plant KVA subsystem is active (see Fig. 225-kVA 7a). Note PV Slave r/slave PV-Slave 1 or 2 could the PV Slave subs PV-Slave 225-kVA 225-kWp 225-kWp Slave 1 Slave 1 225-kVA 225-kVA Bat-Slave 1 225-kVA 450-kVA subsystem 450-kVA subsystem 450-kVA subsystem Bat Master Can use subsystem 1 or subsystem 2 Can use subsystem 1 or subsystem 2 2800-kWh Bat Slave 2800-kWh

(a) daytime utility-tied mode, with PV power greater than user profile.



(c) daytime utility-tied mode, with user profile (greater than 450-kVA) greater than PV power.

(b) daytime utility-tied mode, with user profile (less than 450-kVA) greater than PV power, and stand-alone mode.



(d) nighttime utility-tied mode for battery charging.

FIGURE 7. VARIOUS OPERATING MODES

During hours 10 and 11, the user power profile calls for 450-kW. Only one 450-KVA subsystem is active for this mode, but the battery dc/dc converters (of the active 450-KVA subsystem) are activated to make up the difference between the available PV power and 450-kW (see Fig. 7b). Note that all array power is delivered to the grid and only the shortfall is drawn from the battery (see gray bars in Fig. 6). This direct use of the array power realizes the maximum possible benefit from the array.

The user power profile calls for 750-kW during hours 12 and 13. Both 450-KVA subsystems are active in this mode (see Fig. 7c). One subsystem processes the array power (the battery dc/dc converters are disabled), and the other subsystem processes the battery power. In this mode, one 450-KVA subsystem can deliver up to approximately 375-KVA from the array and the other 450-KVA subsystem can deliver up to 450-KVA from the battery for a total of 825-KVA delivered to the grid. The ability to dispatch the 450-KVA subsystems provides two benefits. First, the power processing system is operated at a higher loading, and therefore at higher efficiencies, at power levels below 450-kWac. In addition, the overall system life is increased by only operating both subsystems when needed.

The battery is then recharged from the utility at night. Both 450-KVA subsystems and all battery dc/dc converters can be activated to charge the battery (see Fig. 7c). The system is designed to provide a full battery recharge each night. The power processing system is designed to provide a taper current charge once the battery reaches its float voltage level.

STAND-ALONE MODE

The power processing system will automatically switch from the utility-tied mode to the stand-alone mode in the event of a utility outage, and it will automatically switch back to the utility-tied mode when utility service is restored. In the event of a utility outage, the power processing system shuts down while the water treatment plant is electrically isolated from the utility grid. The power processing system restarts in a stand-alone mode with the same component configuration as the daytime utility-tied mode (user profile less than PV power). Only one of the 450-KVA subsystems can operate in the stand-alone mode at a time (see Fig. 7b). If the available PV power exceeds the power demand of the water treatment plant, the excess PV power is used to charge the battery through the battery dc/dc converters.

SYSTEM CONTROLLER

The controller is based on a system of microprocessors.

Distributed processors monitor and interface with the subsystems, while a personal computer (PC) collects and analyzes the system status data and then determines the appropriate operating mode for each subsystem. The implementation of the actual subsystem operation of the PV power station is internal to the power processing system. (The isolation of the water treatment plant is implemented by a remote pole-mounted isolation switch.)

For example, during battery charging the PC will collect the battery temperature, current, and voltage, determine the appropriate charge current at that point in time, and then instruct the power processing system to charge the battery at that current. The PC provides manual system control and is used to modify the user power profile and system set points, display system status, and archive performance data. The system can be controlled from a remote computer as well.

CONCLUSIONS

As mentioned earlier, this is a unique system and the implementation of the project was only possible because of some unique circumstances. In the near future, it is not likely that more utility-tied PV powerplants will be installed at other DoD installations. Nevertheless, this project has significantly advanced systems integration and power conditioning technologies, to a point that more large-scale, isolated-grid PV/diesel hybrid powerplant applications can be identified and implemented within DoD. There are hundreds, even thousands, of off-grid DoD facilities which could take advantage of the economical and environmental benefits that these systems have to offer.

Hopefully, the success of this project will also raise awareness within the DoD community of the many other mature PV system technologies, already available for tens of thousands of costeffective applications at their facilities.

REFERENCES

- [1] R. Ducey, "Yuma Proving Ground Plugs Into the Sun," FEMP Focus, June 1997, p. 15.
- [2] M.J. Stern and R.T. West, "Development of a Low-Cost 15 kW A.C. Solar Tracking Sub-Array for Grid-Connected PV Power Applications," *Twenty Fifth IEEE PVSC*, **1996**, pp. 1369-1372.
- [3] R. N. Chapman, "Photovoltaics in the Department of Defense," 14th NREL/SNL Photovoltaics Program Review, American Institute of Physics Conference Proceedings 394, 18-22 November 1996, pp. 491-

511.

[4] R. N. Chapman, "Hybrid Power Technology for Remote Military Facilities," Ninth International Power Quality Solutions/Alternative Energy Conference: Power System World '96 Conference and Exhibit, 9-13 September 1996, pp. 415-427.

AUTHOR'S ADDRESS

Commander, U.S. Army CERL ATTN: CECER-ULU (R. Ducey) P.O. Box 9005 Champaign, IL 61826-9005